- WEATHERIZATION IN ALASKA: A PROVIDERS PERSPECTIVE

PRESENTED BY:

DAN DUAME, EXEC. DIR.
ALEUTIAN HOUSING AUTHORITY

Statewide Wx Program Delivery

AK Legislature mandated the program be implemented 'yesterday.'

- Two delivery networks:
 - 5 Statewide Wx contractors
 - 14 AK Native Regional Housing Authorities





AK Regional HA Background / Structure

- Ak Native organizations created in early 1970's under state statute (A.S. 18.55.996)
- Organized along ANCSA geographic boundaries (service areas)
- Originally formed to meet housing needs of underserved
 Native villages & administer HUD 37' Act funding
- Became TDHE's under NAHASDA
 - □ 190 Tribes
 - Aprox. \$90M in NAHASDA funds

State / Tribal Partnership

- Regional HA's created under same statute as state HA Alaska Housing Finance Corporation (AHFC)
- Pre-existing relationship was critical factor to Wx program development / implementation
 - AHFC supports RHA statewide operations & has on-going contractual relationships
 - $lue{}$ Allowed for immediate conduit / vehicle for Wx service delivery vehicle
 - RHA serve all eligible applicants (Native & non-Native)

- Key to successful Wx program has been well funded, well structured, well implemented training & capacity building program
- RHA already had "construction skills;" Wx skill set had to be added & refined
- AK had core group of energy efficiency experts / energy assessors & trainers to draw from
 - Existing AK Wx program for 20+ years

RHA Contracts included 3 line items:

- Operations
- Administration

Training





AHA Wx training:

- 32 different training sessions to date
- 117 trainings (some staff attending multiple sessions.)
 - E.g.: Lead Construction Coordinator attended 18 sessions; Field Forman attended 5.

- □ 12 different training providers:
 - Alaska Craftsman Home Program; Alaska Works Partnerships; Wisdom & Assoc.; UAA;
 AEA; CCHRC; AHFC; other private contractors
- Broad range of trainings:
 - Advanced Cold Climate building Techniques
 - Energy Assessor certification
 - Combustion safety
 - BPI Certification
 - Boiler / furnace trainings
 - Building envelope retrofitting
 - □ Blower door testing / AKWARM
 - □ Lead Certified Renovator

Wx Program Implementation – Aleutian Housing Examples

Staffing:

- 2 Full-time office employees (Construction & Program Mrg.)
- 12 Full-time field employees
- 9 Part-time field employees (as needed)

■ Process:

- Community Outreach (10 communities)
- Field Assessments (AkWARM driven))
- Develop PMP & Complete Scope of Work (PMP)
- Post-Assessment & Closeout

Projected Wx Projects/ Plans

- □ Current 5-year Plan:
 - Currently in Grant Year 3 under a 5-year plan

- Completed approximately 110 of an anticipated 260-280 projects / units
- Rural area cap of \$30K / unit for S/F units (includes project mgmt., admin & construction)

Field Work Results- Atka







Results – Actual Savings Atka Example

	Pre Weatherization				Post Weatherization			
Wx Client No.	Annual Usage (gallons)	Annual Cost	Cost per gallon	Date data received	Annual Usage (gallons)	Annual Cost	Cost per gallon	Date data received
15	885	\$7,071.00	\$7.99	10/22/08	583	\$3,964.40	\$6.80	1/25/11
13	805	\$6,432.00	\$7.99	9/30/08	350	\$2,380.00	\$6.80	1/25/11
14	402	\$3,212.00	\$7.99	10/22/08	450	\$3,060.00	\$6.80	1/25/11
6	1,200	\$9,588.00	\$7.99	10/13/08	525	\$3,570.00	\$6.80	1/25/11
2	1200	\$9,588.00	\$7.99	12/11/08	620	\$4,216.00	\$6.80	1/25/11
3	400	\$3,196.00	\$7.99	11/25/08	485	\$3,298.00	\$6.80	1/25/11
12	1100	\$8,789.00	\$7.99	8/24/09	300	\$2,040.00	\$6.80	1/25/11
11	835	\$6,671.65	\$7.99	8/24/09	410	\$2,788.00	\$6.80	1/25/11
10	900	\$7,191.00	\$7.99	8/24/09	350	\$2,380.00	\$6.80	1/25/11
8	691	\$5,521.09	\$7.99	8/24/09	425	\$2,890.00	\$6.80	1/25/11
7	712.5	\$5,692.86	\$7.99	8/24/09	510	\$3,468.00	\$6.80	1/25/11
6	800	\$6,392.00	\$7.99	8/24/09	525	\$3,570.00	\$6.80	1/25/11
5	550	\$4,394.50	\$7.99	8/24/09	465	\$3,162.00	\$6.80	1/25/11
13	10,481	\$ 83,739	\$7.99		5,998	\$40,786.40	\$6.80	
	806.19	\$6,441			461	\$3,137.42		

Average homeowner <u>savings</u> in dollars & fuel used: <u>43%</u>

Field Work Results

Project Examples



Installing rigid foam insulation on cement walls

Caulking and air sealing



Finished look





Installing air gasket on electrical outlet

Existing boiler and hot water tank

New System 2000 boiler and hot water tank







Weatherization sticker

New smoke alarm



Back view of smoke alarm (hard wired)





Air Sealed, insulated crawl space

New ground vapor retarder

Prepping attic for cellulose installation



Installed cellulose in attic





New CO detector with digital readout

Sealed air leak at wall penetration in attic

Air sealing at wire penetration in attic





Air sealing and rigid foam insulation in crawl space

Existing HRV with damaged heat exchanger



New HRV replacement





Water damage from leaking windows

Window replacement and siding repair







New exterior exhausting range hood







Existing window jamb - sealed

Stove without range hood exhaust

New range hood exhaust installed





Thank You

CONTACT INFO

Dan Duame, Executive Director

dan.duame@aleutian-housing.com

520 E 32nd Avenue, Anchorage, Alaska 99503

Tel: 907.563.2146 Fax: 907.563.3105

www.aleutian-housing.com

www.ahfc.state.ak.us/



